

Act No. 25, 1910.

SYDNEY WATER
SUPPLY
AMPLIFICATION AND
IMPROVEMENT.

An Act to sanction the carrying out of a scheme for the Amplification and Improvement of the Water Supply of the City of Sydney and Environs ; and for purposes consequent thereon or incidental thereto. [22nd December, 1910.]

Preamble.

WHEREAS in accordance with the provisions of the Public Works Act, 1900, the Legislative Assembly did, by resolution, declare that it was expedient to carry out a certain work, namely, the carrying out of a scheme for the amplification and improvement of the water supply of the City of Sydney and environs: And whereas, on the passing of the said resolution, a statutory duty was by the said Act imposed on the Secretary for Public Works to introduce a Bill into the said Assembly to sanction the carrying out of the said work: Be it therefore enacted by the King's Most Excellent Majesty, by and with the advice and consent of the Legislative Council and Legislative Assembly of New South Wales in Parliament assembled, and by the authority of the same, as follows:—

Short title.

1. This Act may be cited as the "Sydney Water Supply Amplification and Improvement Act, 1910."

Work sanctioned.

2. (1) The carrying out of the work, more particularly described in the Schedule to this Act, is hereby sanctioned, and the Secretary for Public Works, or the member of the Executive Council for the time being performing the duties of the said Secretary, is hereby authorised to undertake and carry out the said work, subject to the provisions of this Act; and for that purpose shall be and shall have the powers and duties of a Constructing Authority within the meaning of the Public Works Act, 1900.

(2) The said work is hereby declared to be a work authorised under the Metropolitan Water and Sewerage Acts, 1880–1889.

Plan of work.

3. The plan of the said work is the plan marked "Improvements to Metropolitan Water Supply Works," signed by the Secretary for Public Works, and countersigned by the Engineer-in-Chief, Metropolitan Board of Water Supply and Sewerage, and deposited in the public office of the said secretary.

4.

Junee Water Supply.

4. The cost of carrying out the said work, estimated at five hundred and fifty-seven thousand seven hundred pounds, may be defrayed from such loan votes as are now, or may hereafter be applicable to that purpose, and shall not, under any circumstances, exceed the estimated cost by more than ten per centum.

SCHEDULE.

THE construction of additional 72-inch trunk main, Pipe Head to Pott's Hill. Additional balance reservoir to hold 150 million gallons at Pott's Hill. Additional mains to supply gravitation water to Cook's River Valley, Illawarra suburbs, Canterbury, Belmore, and water for high-level zones :—

42-inch main from Pott's Hill to Roberts-road.

30-inch main along Cook's River Valley from Roberts-road to junction with existing Illawarra trunk main at Tempe.

36-inch main from Roberts-road to Punchbowl-road.

27-inch main from Punchbowl-road to Canterbury Trust road pumping-station.

24-inch rising main to Penshurst Reservoir.

Pumping-station, engines, &c.
